HNBGU/C&M/2021/ 112 DATED 24-08-2021

H. N. B. Garhwal University, Srinagar (Garhwal)
(a central university)

Notice Inviting Tender
(Under Limited Tender Enquiry GFR-2017 provision-139-V)

Sealed percentage rate tenders on DSR 2019 are invited from registered contractors of HNBGU, for " ***Repairing and Maintenance work in T-12 Residence at Srinagar ".*** Last date of submission of tender**:** 31-08-2021 up to 3.00 P.M. at Construction & Maintenance Department, Srinagar. For detailed information, etc. please contact E. E. Civil HNBGU at Srinagar.

Registrar

NOTICE INVITING TENDER

Last Date of Issue of tender :-
Date of Opening of tender :-
As per sheet attached

This notice may also be seen at websites **www.hnbgu.ac.in**

HNB Garhwal University Srinagar, Garhwal

NOTICE INVITING TENDER

1. Sealed percentage rate tenders on DSR 2019 are invited from registered contractor of HNB Garhwal University, for ***Repairing and Maintenance work in T-12 Residence at Srinagar***. Last date for submission of tender is 31-08-2021 at 03.00 P.M. Construction & Maintenance Department, Srinagar.

NIT No.	S. N0.	Name of work	Estimated cost	Earnest Money	Time allowed	Date of Posting on Notice Board	Last date of issue of tenders & time	Time & date of opening of Tenders	Tender Cost
HNBGU./ C&M /2021/**04**	1.	***Repairing and Maintenance work in T-12 Residence at Srinagar***	₹ 2,99,603/-	Exempted	30 days	24-08-2021	30-08-2021 Up to 4.00 P.M.	31-08-2021 At 3.30 P.M.	NA

The application shall be submitted to the office of Executive Engineer, Construction & Maintenance Department, Srinagar.

The work is estimated to cost as per detail above. This estimate, however, is given merely as a rough guide.

Criteria of eligibility for issue of tender document

1. Tender shall be issued to registered contractor of HNBGU.
2. The time allowed for carrying out the work will be **30 days** from the date of order. However work will be carried out in part as per the requirement of the University.
3. The site for the work is available and ready for commencement of the task.
4. Tender document consisting of plan and specifications of work to be done and the set of terms & conditions of contract to be complied with by the contractor whose tender may be accepted and other necessary documents can be seen in the office of the **EE, HNBGU Srinagar (Garhwal)** between hours of 11:00 A.M. & 04:00 P.M. everyday excepts on Saturday, Sunday and Public Holidays. Tender documents will be issued from his office, during the hours specified above.

5. The sealed tender envelope with the name of work and due date of opening written on envelope, shall be received by the office of EE, HNBGU, Srinagar (Garhwal) Construction &Maintenance Department, Srinagar as per time and date mentioned in page no. 01. The financial bid duly signed by the contractor on the Performa for this purpose as per annexure-1 to be submitted by the contractor in sealed envelope to the office of EE Civil

6. The contractor whose tender is accepted will be required to furnish performance guarantee of 5% (Five percentages) of the tendered amount within the period specified in letter. This guarantee shall be in the form of Deposit at call receipt of any scheduled Bank/Banker's cheque of any scheduled Bank/Demand Draft of any scheduled bank/pay order of any scheduled Bank on prescribed format by University.

In case the contractor fails to deposit the said performance guarantee within the period in letter including the extended period if any, the Money deposited by the registered contractors at the time of registration shall be forfeited automatically without any notice to the contractor.

7. The description of the following works ***"Repairing and Maintenance work in T-12 Residence at Srinagar "*** copies of other drawings and documents pertaining to the works will be open for inspection by the tenderer at the office of E. Engineer, HNBGU, Srinagar.

Tenderers are advised to inspect and examine the site and its surroundings and satisfy themselves before submitting their tenders as to the nature of the ground and sub-soil (so far as is practicable), the form and nature of the site, the means of access to the site, the accommodation they may require and in general shall themselves obtain all necessary information as to risks, contingencies and other circumstances which may influence or affect their tender. A tenderer shall be deemed to have full knowledge of the site whether he inspects it or not and no extra charges consequent on any misunderstanding otherwise shall be allowed. The tenderer shall be responsible for arranging and maintaining at his own cost all materials, tools & plants, water, electricity, access, facilities for workers and all other services required for executing the work unless otherwise specifically provided for in the contract documents submission of a tender by a tenderer implies that he has read this notice and all other contract documents and has made himself aware of the scope and specification of the work to be done.

8. The University through Registrar does not bind itself to accept the lowest or any other tender and reserves to itself the authority to reject any or all of the tenders received without the assignment of any reason. All tenders in which any of the prescribed conditions is not fulfilled or any condition including that of conditional rebate is put forth by the tenderer shall be summarily rejected.

9. Canvassing whether directly or indirectly, in connection with tenders is strictly prohibited and the tenders submitted by the contractors who resort to canvassing will be liable to rejection.

10. The University through Registrar reserves to himself the right of accepting the whole or any part of the tender and the tenderer shall be bound to perform the same at the rate quoted.

11. This Notice Inviting Tender shall form a part of the contract.

Additional Conditions

1**. Scope:**

1.1 The work of **"*Repairing and Maintenance work in T-12 Residence at Srinagar*."** is to be done strictly as per the nomenclature of the item/size as per drawing or as per the direction of Engineer-in-charge.

2. **Specification for work, quality and workmanship**

2.2 All the materials of the work shall confirm to approve makes of material specified (Asian Paints/ Berger Paints/ Shalimar Paints Pvt. Ltd./ Snowcem India ltd). The proof of procurement of various materials shall be provided either from the manufactures or through authorized dealers for first quality of material, if required by university.

2.3 Any damages caused during transit shall be borne by the contractor and nothing shall be paid on this account by university. The damage material shall not be used on the work.

2.4 The quoted rates shall include all taxes i.e. GST and Labour cess etc. The rates shall also include carriage, loading, unloading etc. at site as per the direction of Engineer-in-Charge to the satisfaction of concerned stakeholder/ HOD.

2.5 During the execution of work the contractor shall make necessary arrangements for safe custody of the material on the direction of the Engineer-in-charge till the satisfactory completion of the work.

3. The contractor shall make his own arrangement for obtaining electric connection if required, and make necessary payments directly to the department concerned.

4. The contractor shall fully comply with all legal orders and directions of the Public or local authorities or municipality and abide by their rules and regulations and pay all fees and charges for which he may be liable in this regard. Nothing extra shall be paid/reimbursed for the same. The contractor shall fully responsible for safety measures during work and to comply the directions as per labour act.

5. The deduction for GST, Income Tax and Labour cess shall be made at source as per rules.

6. Satisfactory completion certificate shall have to be obtained from the concerned stack holder/ HOD as per the direction of Engineer-in-Charge. The final payment shall be released only after the satisfactory completion of the task.

A.E. Civil/EE Registrar

Annexure - 1

Performa for Financial bids
Schedule of Quantities

Name of the Work: - ***Repairing and Maintenance work in T-12 Residence at Srinagar***

S. N.	Item Details	Qt.	Unit	DSR 2019 unit rate	Amount/Rate (in ₹)	DSR item
1	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	4.08	cum	1737.45	7088.796	15.2.1
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominal size)	4.68	cum	6,788.60	31770.65	4.1.3
3	Repairs to plaster of thickness 12 mm to 20 mm in patches of area 2.5 sq.metersand under, including cutting the patch in proper shape, raking out joints andpreparing and plastering the surface of the walls complete, including disposalof rubbish to the dumping ground, all complete as per direction of Engineerin-Charge. With cement mortar 1:4 (1 cement : 4 fine sand)	90.00	sqm	417.80	37602.00	13.4.1
4	Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm or more (thickness to be specified by the manufacturer), of 1st quality conforming to IS : 15622, of approved make, in all colours, shades, except White, Ivory, Grey, Fume Red Brown, laid on 20 mm thick Cement Mortar 1:4 (1 Cement : 4 Coarse sand), jointing with grey cement slurry @ 3.3kg/sqm including pointing the joints with white cement and matching pigments etc., complete.	10.00	sqm	1170.70	11707.00	11.40
5	Distempering with 1st quality acrylic distember (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade :Old work (one or more coats)	296.77	sqm	54.30	16114.61	13.90.1
6	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	42.24	sqm	79.95	3377.09	13.99.1
7	Finishing walls with Acrylic Smooth exterior paint of required shade :) Old work (One or more coat applied @ 0.90 ltr/10 sqm).	1040.00	sqm	67.35	70044.00	13.111.2

8	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	20.00	sqm	890.50	17810.00	14.5.1
9	Providing and fixing plywood 4 mm thick, one side decorative veneer conformingto IS: 1328 (type-1), for plain lining / cladding with necessary screws, including priming coat on unexposed surface with : 8.28.1 Decorative veneer facings of approved manufacture	15.00	sqm	1551.00	23265.00	8.28.1
10	Providing and fixing ISI marked flush door shutters conforming to IS :2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters :30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws	8.00	sqm	1,819.80	14558.40	9.21.2
11	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required.(In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works)	120.00	Kg.	131.00	15720.00	10.25.2
12	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With 12 mm mild steel U beading	6.00	sqm	781.25	4687.50	9.51.2
13	Constructing masonry Chamber 30x30x50 cm inside, in brick work in cementmortar 1:4 (1 cement :4 coarse sand) for stop cock, with C. I. surface box100x100 x75 mm (inside) with hinged cover fixed in cement concrete slab 1:2:4mix (1 cement : 2 coarse sand : 4 graded stone aggregate 20 mm nominalsize), i/c necessary excavation, foundation concrete 1:5:10 (1 cement : 5 finesand : 10 graded stone aggregate 40mm nominal size) and inside plasteringwith cement mortar 1:3 (1 cement : 3 coarse sand) 12mm thick, finished with afloating coat of neat cement complete as per standard design :18.32.1 With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	3	no	1,582.45	4747.35	18.32.1

14	Constructing masonry Chamber 60x60x75 cm inside, in brick work in cementmortar 1:4 (1 cement : 4 coarse sand) for sluice valve, with C.I. surface box100mm top diameter, 160 mm bottom diameter and 180 mm deep (inside) withchained lid and RCC top slab 1:2:4 mix (1 cement : 2 coarse sand : 4 gradedstone aggregate 20mm nominal size) , i/c necessary excavation, foundationconcrete 1:5:10 (1 cement : 5 fine sand : 10 graded stone aggregate 40 mm1461 SUB HEAD : 18- WATER SUPPLYnominal size) and inside plastering with cement mortar 1:3 (1 cement : 3 coarsesand) 12 mm thick, finished with a floating coat of neat cement complete asper standard design :18.33.1 With common burnt clay F.P.S.(non modular) bricks of class designation 7.5	1	no	9,288.40	9288.40	18.33.1
15	Sub total			**Rs.**	267780.79	
16	Add cost index @ 8.00%			**Rs.**	21422.46	
17	**Total**			**Rs.**	**289203.26**	
18	Providing and fixing on unplasticised Rigid PVC water pipes. 150 mm diameter	20.00	rmt.	520.00	10400.00	
19	**Grand Total**				299603.26	
20	Percentage rate(below or above to mentioned cost) (- / +)---------%			**Rs.**		
21	**G. Total on offered rates**			**Rs.**		

Signature
Name of the Registered Contractor of the university –
Note :

1. The work shall be completed as per the direction of the engineer in charge.
2. The comparison of the lowest cost of the work shall be made on the basis of overall lowest cost of above task.
3. The above mention quantities are based on approximate estimation. The payment shall be made as per the actual work done.
4. Other items, if carried out by the direction of engineer in charge will be paid accordingly on accepted percentage rates of DSR.

A.E civil /E. Engineer Registrar